

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण खण्ड-अष्टम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 मद में सेमी-टर्नकी के अघार पर प्रणाली सुदृढीकरण का कार्य आदि ई-निविदा द्वारा वाह्य एजेन्सी के माध्यम से कराने का कार्य।

Contract No: 0120 2607114

Name of the Bidder/

PRICE SCHEDULE FOR E-TENDER NO-32/W/2023-24/EUDD-8/EUDC-2/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable

NUMBER	TEXT #	NUMBER	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय वितरण खण्ड-अष्टम, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान 2024-25 मद में सेमी-टर्नकी के अघार पर प्रणाली सुदृढीकरण का कार्य आदि ई-निविदा द्वारा वाह्य एजेन्सी के माध्यम से कराने का कार्य।						
1.01	Safe Carriage of LT XLPE Cable AL. 1x630 Sq.mm from PVVNL Store Sahibabad/Ghaziabad/ Noida to site of work including loading & unloading at both side.	11400	Mtr.	INR		0.00	INR Zero Only
1.02	Safe Carriage of LT XLPE Cable AL. 1x1000 Sq.mm from PVVNL Store Sahibabad/Ghaziabad/ Noida to site of work including loading & unloading at both side.	750	Mtr.	INR		0.00	INR Zero Only
1.03	Safe Carriage of LT XLPE Cable AL. 1x400 Sq.mm from PVVNL Store Sahibabad/Ghaziabad/ Noida to site of work including loading & unloading at both side.	1450	Mtr.	INR		0.00	INR Zero Only
1.04	Safe Carriage of LT XLPE Cable AL. 1x70 Sq.mm from PVVNL Store Sahibabad/Ghaziabad/ Noida to site of work including loading & unloading at both side.	6800	Mtr.	INR		0.00	INR Zero Only
1.05	Safe Carriage ACSR Dog Conductor from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	2650	Mtr.	INR		0.00	INR Zero Only
1.06	Safe Carriage of line accessories such as 04 No. ST Pole 11 Meter SP-55, 465 No. D.O. Fuse Set 11 KV, 134 No. 11 KV Composite Polymeric Pin Insulator and 63 No. 11 KV V-Type Steel Cross Arm (65x65x6mm) from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side..	1	Job.	INR		0.00	INR Zero Only
1.07	Laying of LT XLPE Cable AL. 1x630 Sq.mm. completion of work as per requirement of site.	11400	Mtr.	INR		0.00	INR Zero Only
1.08	Laying of LT XLPE Cable AL. 1x1000 Sq.mm. completion of work as per requirement of site.	750	Mtr.	INR		0.00	INR Zero Only
1.09	Laying of LT XLPE Cable AL. 1x400 Sq.mm. completion of work as per requirement of site.	1450	Mtr.	INR		0.00	INR Zero Only
2.00	Laying of LT XLPE Cable AL. 1x70 Sq.mm. completion of work as per requirement of site.	6800	Mtr.	INR		0.00	INR Zero Only
2.01	Laying of ACSR Dog Conductor. completion of work as per requirement of site.	850	Mtr.	INR		0.00	INR Zero Only
2.02	Dismantling of Old/Damaged 11 KV HT AB Cable.	850	Mtr.	INR		0.00	INR Zero Only
2.03	Erection, Grouting, Concreting & Installation of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	4	No.	INR		0.00	INR Zero Only
2.04	Providing and FIXING Chemical Earthing with Terminal Hole. 8mm. Service Life-Up to 12 Years. Terminal Size. 50mm x 6mm Earthing work upto 10 Feet depth. 90mm Galvanized Iron (GI) Chemical Earthing Electrode.	1222	No.	INR		0.00	INR Zero Only
2.05	Erection/Fixing of DO Fuse set 11 KV	465	No.	INR		0.00	INR Zero Only
2.06	PROVINDING AND FIXING of LT ACB 4 Pole 800 Amp. (SCHNEIDER MAKE)	14	No.	INR		0.00	INR Zero Only
2.07	PROVINDING AND FIXING of LT ACB 4 Pole 630 Amp. (SCHNEIDER MAKE)	257	No.	INR		0.00	INR Zero Only
2.08	PROVINDING AND FIXING of LT ACB 4 Pole 1250 Amp. (SCHNEIDER MAKE)	1	No.	INR		0.00	INR Zero Only
2.09	FIXING of 11 KV V-Type Steel Cross Arm 65x65x6 mm	63	No.	INR		0.00	INR Zero Only
3.00	PROVINDING AND FIXING MS Channel 100x50x5 MM.	150	Kg.	INR		0.00	INR Zero Only
3.01	PROVINDING AND FIXING Cross Arm Holding Clamp with Nut & Bolts	63	No.	INR		0.00	INR Zero Only
3.02	PROVINDING AND FIXING G.I. Strip of size 25x3 mm	1068	Kg.	INR		0.00	INR Zero Only
3.03	PROVINDING AND FIXING Tinned Copper Fuse Wire 22 SWG	20	Kg.	INR		0.00	INR Zero Only
3.04	PROVINDING AND FIXING Tinned Copper Fuse Wire 24 SWG	20	Kg.	INR		0.00	INR Zero Only
3.05	PROVINDING AND FIXING Tinned Copper Fuse Wire 26 SWG	30	Kg.	INR		0.00	INR Zero Only
3.06	PROVINDING AND FIXING Aluminium Lug 70 Sq.mm	3680	No.	INR		0.00	INR Zero Only
3.07	PROVINDING AND FIXING Aluminium Lug 400 Sq.mm	348	No.	INR		0.00	INR Zero Only
3.08	PROVINDING AND FIXING Aluminium Lug 630 Sq.mm	2736	No.	INR		0.00	INR Zero Only
3.09	PROVINDING AND FIXING Aluminium Lug 1000 Sq.mm	208	No.	INR		0.00	INR Zero Only
4.00	PROVINDING AND FIXING Aluminium Bus Bar 850x75x12 mm LT Distribution	4352	No.	INR		0.00	INR Zero Only
4.01	PROVINDING AND FIXING Nutt & Bolts with washer off size	544	Kg.	INR		0.00	INR Zero Only
4.02	PROVINDING AND FIXING Panel Fabrication 1250x900x600 mm 14 GUA	272	No.	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only	