

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: गाजियाबाद क्षेत्र-मृतीय, गाजियाबाद के अन्तर्गत समस्त वितरण खण्डों के कार्यक्षेत्रों में 33 कोवी0 एवं 11 कोवी0 के भूमिगत केबिलों में होने वाले फॉल्टों को अटैच कर मरम्मत करने का कार्य वित्तीय वर्ष 2024-25 के ओ0 एण्ड एफ0 मद में ई-निविदा द्वारा बाध्य एजेन्सी के माध्यम से कराया जाना। Qty. of individual item variation $\pm 20\%$.

Contract No: 0120 2607114

PRICE SCHEDULE FOR E-TENDER NO-01/W/2024-25/ZONE-3/EUDC-II/GZB									
*(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable									
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	BASIC RATE In Figures To be entered by the Bidder Rs. P	Quoted Currency in INR / Other Currency	Units	Quantity	TOTAL AMOUNT Without Taxes
Sl. No.	Item Description								TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8		
1.00	Location and pin pointing of cable fault exposing the same in the underground 33 KV and 11 KV cable including digging of trench upto the depth of the cable, cutting the faulty cable and sealing of the faulty cable, high pressure testing of cable (Cable fault location equipment & other Infrastructure like vehicle will be provided by the department). Qty. of individual item variation $\pm 20\%$.								
1.01	33 KV cable fault location (Size of trench 4 m length & 1.5 m width).	160	No.	INR		0.00	INR Zero Only		
1.02	Providing Jointer per 33 KV Joint for making joints.	160	No.	INR		0.00	INR Zero Only		
1.03	11 KV cable fault location (Size of trench 3 m length & 1.5 m width).	150	No.	INR		0.00	INR Zero Only		
1.04	Providing Jointer per 11 KV Joint for making joints.	150	No.	INR		0.00	INR Zero Only		
1.05	On locating & Pin-Pointing of cable fault, digging the cable trench of suitable size in deep up to 2meter or as per site requirement so as to enable for making of cable jointing in pakka road (Hard soil) with the help of road cutter/digging machine. Tractor	1400	Cubic Meter	INR		0.00	INR Zero Only		
1.06	Replacement of 33 KV of damaged cable (84 meter) (cable shall be provided by the depratment).	150	No.	INR		0.00	INR Zero Only		
1.07	Replacement of 11 KV of damaged cable (167 meter) (cable shall be provided by the depratment).	190	No.	INR		0.00	INR Zero Only		
Total in Figures									
Quoted Rate in Words							INR Zero Only		