

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान वर्ष 2024-25 के मद में 33 कोवी0 एवं 11 कोवी0 लाईन निर्माण एवं बाइफरकेशन आदि कार्य सेमी-टर्नकी के आधार पर ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने हेतु।

Contract No: 0120 2607114

Name of the Bidder/		PRICE SCHEDULE FOR Re-TENDER NO-29/W/2023-24/EUDC-2/GZB						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable								
NUMBER	TEXT #	NUMBE	TEXT	TEXT #	NUMBER #	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantit y	Units	Quoted Currency In INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1.00	विद्युत नगरीय वितरण मण्डल-द्वितीय, गाजियाबाद के कार्यक्षेत्र में बिजनेस प्लान वर्ष 2024-25 के मद में 33 कोवी0 एवं 11 कोवी0 लाईन निर्माण एवं बाइफरकेशन आदि कार्य सेमी-टर्नकी के आधार पर ई-निविदा द्वारा बाह्य एजेंसी के माध्यम से कराने हेतु।							
1.01	Safe Cartage of 29 No. ST Pole 11 Mtrs. Long 17 No. ST Pole 13 Meter Long from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	46	No.	INR		0.00	INR Zero Only	
1.02	Carriage of 11 KV HT Cable 3x185 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	5755	Mtr.	INR		0.00	INR Zero Only	
1.03	Carriage of 11 KV HT Cable 3x300 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	2818	Mtr.	INR		0.00	INR Zero Only	
1.04	Carriage of XLPE Cable 3x120 Sq.mm. from PVVNL Store Sahibabad/ Ghaziabad/ Noida to site of work including loading & unloading at both side.	900	Mtr.	INR		0.00	INR Zero Only	
1.05	Carriage of 190 Meter Aluminium Cable XLPE 3x70 Sq.mm, 82 No. 11 KV Outdoor and 02 No. Indoor Cable Box of 3x185 Sq.mm. and 42 No. 33/11 KV Outdoor Cable Box of 3x300 Sq.mm, 02 No. 33/11 KV Sgtraight Through of 3x300 Sq.mm, 18 No. Outdoor Cable Box of 3x120 Sq.mm and 04 No. Aluminium Cable Jointing Kit 3x70 Sq.mm from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only	
1.06	Carriage of ACSR Dog Conductor from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work including loading & unloading at both side.	5590	Mtr.	INR		0.00	INR Zero Only	
1.07	Carriage of 01 No. 11 KV VCB O/G CTR 400/200/5 A 24 V (CG Make) from PVVNL Store Sahibabad/Ghaziabad/Noida to site of work and fixing/installation of the same at site and complete the work as per requirement of site including loading & unloading at both side.	1	No.	INR		0.00	INR Zero Only	
1.08	Installation of 11 KV VCB O/G CTR 400/200/5A 24 V (CG Make). Complete Work as per requirement of site.	1	No.	INR		0.00	INR Zero Only	
1.09	Carriage of line accessories such as 15 No. 11 KV Disc Insulator 45KN with fitting(15), 30 No. 11 KV Polymeric PIN Insulator, 01 No. DO Fuse Set 11 KV and 12 No. Earth Rod (2540x20mm), 60 No. 11 KV V-Type Steel Cross Arm, from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only	
2.00	Carriage of material such as 02 No. 33 KV Line Isolator, 15 No. 33 KV Disc Insulator, 09 No. 33 KV Disc with Nutt, 40 No. 33 KV Pin Insulator, 21 No. 33 KV Pin with Nutt, 10 No. 33 KV V-Type Steel Cross Arm, from PVVNL Store Sahibabad/ Ghaziabad/Noida to site of work including loading & unloading at both side.	1	Job.	INR		0.00	INR Zero Only	
2.01	Installation/Fixing of Outdoor Cable Box 11 KV 3x185 Sq.mm	82	No.	INR		0.00	INR Zero Only	
2.02	Installation/Fixing of Indoor Cable Box 11 KV 3x185 Sq.mm	2	No.	INR		0.00	INR Zero Only	
2.03	Installation/Fixing of Outdoor Cable Box 11 KV 3x300 Sq.mm	42	No.	INR		0.00	INR Zero Only	
2.04	Installation/Fixing of Straight Through 3x300 Sq.mm	2	No.	INR		0.00	INR Zero Only	
2.05	Installation/Fixing of Outdoor Cable Box 11 KV 3x120 Sq.mm	18	No.	INR		0.00	INR Zero Only	
2.06	Installation/Fixing of Aluminium Cable Jointing Kit 3x70 Sq.mm	4	No.	INR		0.00	INR Zero Only	
2.07	Erection, Grouting, Concreting & Installation of Double Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	10	No.	INR		0.00	INR Zero Only	
2.08	Erection, Grouting, Concreting & Installation of Single Pole Structure including all the accessories to be mounted on pole and proper completion of work as per requirement of site.	26	No.	INR		0.00	INR Zero Only	
2.09	Laying/Erection of ACSR Dog Conductor. Proper completion of work as per requirement of site.	2500	Mtr.	INR		0.00	INR Zero Only	
3.00	Laying of 11 KV HT Cable of 3x185 Sq.mm with Trenchless method by providing of HDPE Pipe and proper completion of work as per requirement of site.	4050	Mtr.	INR		0.00	INR Zero Only	
3.01	Normal Laying of 11 KV HT Cable of 3x185 Sq.mm. Proper completion of work as per requirement of site.	1305	Mtr.	INR		0.00	INR Zero Only	
3.02	Laying of 11 KV HT Cable of 3x120 Sq.mm with Trenchless method by providing of HDPE Pipe and proper completion of work as per requirement of site.	350	Mtr.	INR		0.00	INR Zero Only	
3.03	Normal Laying of 11 KV HT Cable of 3x120 Sq.mm. Proper completion of work as per requirement of site.	200	Mtr.	INR		0.00	INR Zero Only	
3.04	Laying of 11 KV HT Cable of 3x300 Sq.mm. with Sand and Brick. Proper completion of work as per requirement of site.	680	Mtr.	INR		0.00	INR Zero Only	
3.05	Laying of 11 KV HT Cable of 3x300 Sq.mm with Trenchless method by providing of HDPE Pipe and proper completion of work as per requirement of site.	600	Mtr.	INR		0.00	INR Zero Only	
3.06	Installation/Fixing of 33 KV Line Isolator. Complete Work as per requirement of site.	2	No.	INR		0.00	INR Zero Only	

3.07	Febrication of 33 KV Line Isolator. Complete Work as per requirement of site.	2	No.	INR		0.00	INR Zero Only
3.08	Concreting of 33 KV Line Isolator. Complete Work as per requirement of site.	2	No.	INR		0.00	INR Zero Only
3.09	Fixing/Installation of D.O. Fuse Set. Complete work as per requirement of site.	1	No.	INR		0.00	INR Zero Only
4.00	Providing and FIXING Chemical Earthing with Terminal Hole. 8mm. Service Life-Up to 12 Years. Terminal Size. 50mm x 6mm Earthing work upto 10 Feet depth. 90mm Galvanized Iron (GI) Chemical Earthing Electrode.	4	No.	INR		0.00	INR Zero Only
4.01	Earthing of pole by providing Earth Rod (2540x20mm)	24	No.	INR		0.00	INR Zero Only
4.02	Providing and Fixing of Stay Set.	8	No.	INR		0.00	INR Zero Only
4.03	Providing and Fixing of Stone Pad.	16	No.	INR		0.00	INR Zero Only
4.04	PROVINDING AND FIXING MS Channel 100x50x5 MM.	1700	Kg.	INR		0.00	INR Zero Only
4.05	PROVINDING AND FIXING MS Channel 125x65x5 MM.	660	Kg.	INR		0.00	INR Zero Only
4.06	PROVINDING AND FIXING Danger Board with Clamp for 11 KV	4	No.	INR		0.00	INR Zero Only
4.07	PROVINDING AND FIXING Number Plate with Clamp for 11 KV	2	No.	INR		0.00	INR Zero Only
4.08	PROVINDING AND FIXING HDPE Pipe 6 Inch Dia.	490	Mtr.	INR		0.00	INR Zero Only
4.09	PROVINDING AND FIXING GI Pipe 6 Inch Dia for XLPE Cable.	227	Mtr.	INR		0.00	INR Zero Only
5.00	PROVINDING AND FIXING G.I. Wire 6 SWQ.	10	Kg.	INR		0.00	INR Zero Only
5.01	PROVINDING AND FIXING G.I. Strip 50x6 mm..	24	Kg.	INR		0.00	INR Zero Only
5.02	PROVIDING AND FIXING Nut & Bolt with washer off Size as per RESPO.	163	Kg.	INR		0.00	INR Zero Only
5.03	PROVIDING AND FIXING M.S. Hosding Clamps.	192	No.	INR		0.00	INR Zero Only
5.04	PROVIDING AND FIXING STP Pole Clamp with Nutt	62	No.	INR		0.00	INR Zero Only
5.05	PROVIDING Aluminium Paint and Red Oxide Paint and paiting of poles minimum 10 feet above ground level.	20	No.	INR		0.00	INR Zero Only
5.06	Dismantling of old and damaged Dog Conductor and carriage to JE Store/Store Center Sahibabab/Ghaziabad. Loading and unloading at both ends.	2500	Mtr.	INR		0.00	INR Zero Only
5.07	Old and Used XLPE Cable carriage to JE Store/Store Center Sahibabab/Ghaziabad. Loading and unloading at both ends.	300	Mtr.	INR		0.00	INR Zero Only
5.08	Febrication of Double Pole.	2	No.	INR		0.00	INR Zero Only
Total in Figures		INR Zero Only					
Quoted Rate in Words							