

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Superintending Engineer, EUDC-II, Ghaziabad (U.P)

Name of Work: अधिशासी अभियन्ता, विद्युत नगरीय वितरण खण्ड-33 के०वी० (तकनीकी) ट्रान्स हिण्डन, गाजियाबाद के कार्यक्षेत्र में लाईन सम्बन्धी कार्य पूर्ण जमा योजना मद में कराने हेतु बाह्य एजेंसी के माध्यम से कराये जाने का कार्य।

Contract No: S193320600

Name of
the
Bidder/
Bidding

PRICE SCHEDULE FOR E-TENDER NO-02/W/2025-26/D-33KV/LT-MNGR/GZB

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) GST EXTRA as applicable

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.00	विद्युत नगरीय वितरण खण्ड-33 के०वी० (तकनीकी) ट्रान्स हिण्डन, गाजियाबाद के कार्यक्षेत्र में लाईन सम्बन्धी कार्य पूर्ण जमा योजना मद में कराने हेतु बाह्य एजेंसी के माध्यम से कराये जाने का कार्य।						
1.01	13 Mtr./11 Mtr./9 Mtr./8.5 Mtr. Long PCC/ST Poles.	25	No.	INR		0.00	INR Zero Only
1.02	ACSR Weasel/Dog Conductor.	98	Meter	INR		0.00	INR Zero Only
1.03	33 KV XLPE cable of size 3x70 sq.mm./ 3x120 sq.mm./ 3x180 sq.mm./3x400 sq.mm. etc.	800	Meter	INR		0.00	INR Zero Only
1.04	Line-material such as Cross-Arms, Pin Insulators, Guarding Angles, Guarding Wire, Disc Insulators and Cable Jointing Kits etc.	300	No.	INR		0.00	INR Zero Only
1.05	Replacement of CT/PT Unit	5	No.	INR		0.00	INR Zero Only
1.06	33 KV pilfer proof metering cubical.	5	No.	INR		0.00	INR Zero Only
1.07	Dismantling of the line. Removing of ACSR Weasel/Dog conductor from all phases on line, making bundle and stacking at a safe place.	1000	Meter	INR		0.00	INR Zero Only
1.08	Uprooting of 13 Mtr./11 Mtr./9 Mtr./8.5 Mtr. Long PCC/ST Poles.	25	No.	INR		0.00	INR Zero Only
1.09	For 33 KV Line, Single support 13/11/9/8.5 Mtr. long ST/PCC Poles :- Excavation of foundation pit in size of 75x45 cm. having depth of 1/6th of the full length of the support (pole), providing and laying of stone pad (300x300x75mm.) in the bottom of the pit. Erection of support (pole) complete with fixing of 33 KV V-Type cross-arms and all other accessories by providing stone pad, cross arms, holding clamps, f-bracket and nuts & bolts etc. as per RESPO Norms.	5	No.	INR		0.00	INR Zero Only
2.00	For 33 KV Line, Single support 13/11/9/8.5 Mtr. long ST/PCC Poles :- Excavation of foundation pit in size of 75x45 cm. having depth of 1/6th of the full length of the support (pole). Erection of support (pole) complete work by fixing of D.P. Clamps and all other accessories. The work includes fabrication work and fixing of cross bracing sets, cutting holes complete work as per RESPO Norms.	15	No.	INR		0.00	INR Zero Only

2.01	Construction of Tri-Pole Structure on ST Poles including fabrication of MS Angle Channel, Cross Bracing etc. with proving and fitting of all type of clamps made of MS Flat of size 65x8mm. with Nuts, Bolts & washer, grouting of pole in size of 220x45x45 cm. with Cement, Sand and Brick Ballast in the ratio of 1:4:8, as per RESPO Norms.	15	No.	INR		0.00	INR Zero Only
2.02	Grouting of Poles Single line support :- Grouting of support in CC 1:4:6 (cement, sand and 40 mm. brick ballast) Grouting will be done in the block of size 45cm x 45cm x 1/6th of full length of the support upto ground level as per RESPO Norms.	25	No.	INR		0.00	INR Zero Only
2.03	Grouting of stay rods (20x1800mm.) including all works of excavation, cement concrete in size of (0.60x0.60x0.30)m in the ratio of 1:4:6 (cement, sand and 40 mm. brick ballast) including back filling of soil and proper ramming etc.	25	No.	INR		0.00	INR Zero Only
2.04	Fixing, tightening and nozzelling of stay wire with stay rod and stay insulators with the pole of required tension by providing stay clamps, nuts, bolts etc.	25	No.	INR		0.00	INR Zero Only
2.05	Earthing of support with MS Earth Rod of (20x2500)mm. long including excavation of pit and driving MS Rod 3.0M apart from support and 0.5M below the ground level and connecting below the earth electrodes with the help of G.I. Wire No.6 SWG tightening with nuts and bolts.	50	No.	INR		0.00	INR Zero Only
2.06	Laying, sagging, stringing and binding of ACSR Weasel/ Dog Conductor with all other accessories on pole as per RESPO Norms.	1000	Meter	INR		0.00	INR Zero Only
2.07	Filling and fixing of 33 KV outdoor/indoor type cable jointing kits as per RESPO Norms.	30	No.	INR		0.00	INR Zero Only
2.08	Construction of 33 KV Underground Line :- Digging of cable trench in size of 0.45Mtr.x1.05 Mtr.	150	Meter	INR		0.00	INR Zero Only
2.09	Laying of 33 KV 3x70/120/185/400 sq.mm. cable in the trench.	800	Meter	INR		0.00	INR Zero Only
3.00	Refilling and ramming of the left out soil, closing and trench and levelling. Spare cable shall be left in the loop shape at both ends, including providing of all required material and T&P.	100	Meter	INR		0.00	INR Zero Only
3.01	Providing and fixing of Danger Board with clamp, nut and bolts.	50	No.	INR		0.00	INR Zero Only
3.02	Providing and fixing of Number Plate with clamp, nut and bolts.	50	No.	INR		0.00	INR Zero Only
3.03	Providing and wrapping of barbed wire on 33 KV PCC Poles at a height of 2.75 Mtr. from the ground level as per RESPO Norms.	100	No.	INR		0.00	INR Zero Only
3.04	Fitting of 33 KV Piller proof metering cubical including making proper connections.	0.00	No.	INR		0.00	INR Zero Only
3.05	Guarding of 33 KV Line with G.I. wire as per RESPO Norms.	0.00	No.	INR		0.00	INR Zero Only
3.06	Mounting and fixing of 33 KV CT/PT Unit on double pole including making proper connections.	8	No.	INR		0.00	INR Zero Only
3.07	Providing G.I. Pipe 6" dia for inserting 33 KV XLPE cable for safety of cable on Single/Double Pole by providing and fixing of MS Clamp, Nuts and Bolts.	60	No.	INR		0.00	INR Zero Only
3.08	Carriage of following from work site to Store Centre including loading and unloading at both ends :- 13 Mtr./11 Mtr./9 Mtr. Long ST Poles.	25	No.	INR		0.00	INR Zero Only
3.09	ACSR Weasel/Dog Conductor/M.S. Scrap.	1000	No.	INR		0.00	INR Zero Only
4.00	CT/PT Unit.	6	No.	INR		0.00	INR Zero Only
4.01	33 KV pilfer proof metering cubical.	6	No.	INR		0.00	INR Zero Only
4.02	Providing and fixing of Aluminium Paint.	20	Kg.	INR		0.00	INR Zero Only
4.03	Providing and fixing of Red Oxide Paint.	20	Kg.	INR		0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only	